

**PROPOSED DECOMMISSIONING OF DUMPSITE, CONSTRUCTION OF TRANSFER STATION AND OTHER CIVIL WORKS AT ATHI RIVER EPZ - LOT 1 (MAIN CIVIL WORKS) - EPZA TENDER NO. 12/2016-2017.**

ITEM NO.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	<b><u>BILL NO. 1: GENERAL &amp; PRELIMINARIES</u></b>				
A	Allow for preliminaries of mobilization and set up, storage facilities etc ,minor preparatory works and compliance with conditions of contract.	ITEM			
B	Allow a Prime Cost Sum of ksh 500,000 for Project Manger's supervision expenses and offsite material testing to be expended as directed by the Project Manager.	SUM			500,000
C	Include a percentage of Prime Cost sum in item B above for Contractor's overheads and profit.	%			
D	Allow a Prime Cost Sum of Ksh 600,000 for County and other relevant Approvals to be expended as directed by the Project Manager.	SUM			600,000
E	Include a percentage of Prime Cost sum in item D above for Contractor's overheads and profit.	%			
F	Allow a Prime Cost Sum of Ksh 400,000 to cater for Clerk of Works/Works Inspector expenses to be expended as directed by the Project Manager.	SUM			400,000
G	Include a percentage of Prime Cost sum in item F above for Contractor's overheads and profit.	%			
H	Provide and maintain project publicity sign board as directed by the Project Manager in accordance with MoR&PW drawing No. SS/234.	NO	1		
<b>TOTAL CARRIED TO SUMMARY PAGE</b>					

**PROPOSED DECOMMISSIONING OF DUMPSITE, CONSTRUCTION OF TRANSFER STATION AND OTHER CIVIL WORKS AT ATHI RIVER EPZ - LOT 1 (MAIN CIVIL WORKS) - EPZA TENDER NO. 12/2016-2017.**

<b>BILL NO. 2: EARTHWORKS</b>					
A	Excavate, load and cart away all the dumped soil material (soft) and dispose off at an approved dump site outside the EPZA zone. Rate to include cost of haulage of the same to a distance of more than 5km.	CM	75500		-
B	Compact the top 150mm layer of existing ground below the stripped level to 95% MDD (AASHTO T99). Rate to include cost of grading and levelling the site as well as watering during compaction.	CM	4117		-
C	Excavate, load and cart away all excavated material to form composting pit and dispose off at an approved dump site outside the EPZA zone. Rate to include cost of haulage to a distance of more than 5km.	CM	12968		-
D	Provide, lay and compact approved neat gravel material (CBR = 30) as riding surface to a thickness of 300mm in layers of 150mm at 95% MDD.	CM	3000		-
<b>TOTAL CARRIED TO SUMMARY PAGE</b>					<b>-</b>

**PROPOSED DECOMMISSIONING OF DUMPSITE, CONSTRUCTION OF TRANSFER STATION AND OTHER CIVIL WORKS AT ATHI RIVER EPZ - LOT 1 (MAIN CIVIL WORKS) - EPZA TENDER NO. 12/2016-2017.**

<b><u>SUMMARY PAGE</u></b>				
Carried from page 1				-
Carried from page 2				-
<b>Sub-Total I</b>				<b>-</b>
Allow Provisional Sum of Ksh30,000,000 for the construction of waste transfer station and associated works comprising of but not limited to the fence,gates, gate house etc to be expended as directed by the Project Manager.				30,000,000
Allow Provisional Sum of Ksh 10,000,000 for Contigencies to be expended in part or in whole as directed by the Project Manager.				10,000,000
<b>Sub-Total II</b>				<b>40,000,000</b>
<b>TOTAL CARRIED TO MAIN SUMMARY PAGE (Sub-Total I + Sub-total II)</b>				